YOUR LOGO

JobsiteBooked Construction

1120 Industrial Park Rd, Springfield, IL 62702

(217) 555-0148 · office@jobsitebookedconstruction.example

License number 104.000000 (sample) · Insurance general liability and workers' comp, certificate on request

ROOFING QUOTE

QUOTE NUMBER 1042

DATE November 18, 2026

GOOD UNTIL December 18, 2026 (30 days; material prices move)

CUSTOMER AND JOB

Customer
Dana Whitfield

Job address
418 Maple Hollow Dr, Springfield, IL 62704

Phone and email
(217) 555-0193 · dana.whitfield@example.com

THE ROOF

Roof type and pitch
Hip roof, two valleys, 6/12 pitch

Roof area (1 square = 100 sq ft)
22 squares, measured

Priced on
24 squares, including waste

Layers to remove
1 layer of asphalt shingles

Vents, chimneys, skylights, pipes
1 chimney, 3 pipe boots, 4 box vents

Photos taken
6 (attached)

SCOPE OF WORK

What we'll do

Tear off to the deck and inspect the decking. Install ice and water shield, new underlayment, drip edge, starter strip, shingles, flashing at the chimney and pipes, new box vents and ridge cap. Haul away all debris and magnet-sweep the yard for nails.

What's left out

Gutters, fascia and soffit repair, skylight replacement, interior ceiling repair.

MATERIALS

Roofing
Option B, Owens Corning Duration architectural shingles, color Onyx Black (Options A and C: color picked at signing)

Underlayment
Synthetic, over the whole deck

Ice and water shield where
Along the eaves and in both valleys

Ventilation
☐ keep as is ☑ replace with 4 new box vents

Flashing and edges
New chimney flashing, new pipe boots, new drip edge

LINE ITEMS per option

Item	OPTION A — 3-tab shingle roof		OPTION B — Architectural shingle roof (RECOMMENDED)		OPTION C — Steel standing-seam metal roof	
	Qty × unit price	Amount	Qty × unit price	Amount	Qty × unit price	Amount
Tear-off and haul, 1 layer	22 sq × $125	**$2,750**	22 sq × $125	**$2,750**	22 sq × $125	**$2,750**
Roofing installed	3-tab shingles installed (with the materials above) 24 sq × $425	**$10,200**	Architectural shingles installed (with the materials above) 24 sq × $500	**$12,000**	Steel standing-seam panels installed (underlayment, trim, closures) 24 sq × $1,000	**$24,000**
Dumpster and dump fees	1 job × $600	**$600**	1 job × $600	**$600**	1 job × $600	**$600**
Building permit	1 job × $350	**$350**	1 job × $350	**$350**	1 job × $350	**$350**
Option total		**$13,900**		**$15,700**		**$27,700**

ROOFING QUOTE

QUOTE NUMBER 1042

ADD-ONS

- [x] Decking repair, up to 3 sheets, priced now so work doesn't stop — $450
- [ ) _____ $ _____

TOTALS Option B picked

Subtotal	$15,700
Add-ons	$450
Discount	$0
Tax	$0
	tax on materials is in our prices
Total	**$16,150**
Deposit to book the job	$1,000
Balance due on completion	$15,150

WARRANTY

Manufacturer warranty on materials: Owens Corning Standard Product Limited Lifetime, 10 years non-prorated (Option B)

Our workmanship warranty: 5 years on leaks caused by installation

TERMS

- Rotted or soft decking found after tear-off, beyond any sheets priced above, is priced on its own estimate. That work starts only once you sign it.
- Changes: any other change to the work is written down, priced and signed by you before we do it.
- Weather can move the start date. We confirm the day by text the day before.
- Payment: deposit on signing, balance due on completion.
- Right to cancel: if you sign this at your home, you can cancel until midnight of the third business day after you sign. Two copies of the cancellation form are attached.
- This quote is good until the date above.

APPROVAL

Option picked [ ) A [x] B [ ) C Add-ons: decking repair

Customer signature	Date	Contractor signature	Date

Printed name	Printed name and title
Dana Whitfield	Sam Ortega, owner